



2522 Kansas Avenue • Riverside, CA 92507 USA

December 12, 2022

This is to certify that the Purpose of Test, Description of Test Unit, Load Test on ANSI/SCTE 77-2013- Tier 22 Series and corresponding results as related in American Enclosures report of test titled:

LOAD TESTING CERTIFICATION
ANSI/SCTE 77-2013- Tier 22 SERIES
Loading Tests
APC243624

Test Date: November 15, 2022

Depict a true and factual account of events to the best of my knowledge and belief.

Authorized Testing, Inc.

By


Derek R. Gaytan, Quality Manager

A Notary Public or other officer completing this certificate verifies only the identity of the individual who signed the document to which this certificate is attached, and not the truthfulness, accuracy, or validity of that document.

STATE OF CALIFORNIA


} ss.

COUNTY OF RIVERSIDE

On this the **12th** day of **December 2022**, before me **ALISSA M. GRIMES**, the undersigned Notary Public, personally appeared **Derek R. Gaytan**, who proved to me on the basis of satisfactory evidence to be the person whose name is subscribed to the within instrument and acknowledged to me that he executed the same in his authorized capacity, and that by his signature on the instrument the person, or entity upon behalf of which the person acted, executed the instrument.

I certify under PENALTY OF PERJURY under the laws of the State of California that the foregoing paragraph is true and correct.

WITNESS my hand and official seal.




Notary Public

JH American Enclosures LLC
8330 E Hwy 67 Bldg C
Alvarado, TX 76009
Jh_american@yahoo.com

JH American Enclosures
Made from over 30 years of experience

Product Compliance Analysis

Date: 11/15/22 Time _____ **Product Compliance Analysis**

Laboratory Personnel: _____ Position: _____

Item Description: RPC 243624 Polymer Concrete

Test Specification: ANSI/SCTE 77-2013 ☐ Tier 15 ☒ Tier 22 Referenced Work Instruction: ANSI/SCTE 77-2013

Calibrated Instruments: Tara T1504079 Load Cell – Miltutoyo Digital Indicator SN 17206067 Or SN 19228292

Vertical Cover Load	Cycle #	Design Load Requirement (lbs)	Design Load Results (lbs)	Deflection (0.500 max)	Results (P/F)
Vertical Design load	1	22k	22,540	.1928	P
Vertical Design load	2	22k	22,460	.2265	P
Vertical Design load	3	22k	22,460	.2465	P
Vertical Design load	4	22k	22,168	.2489	P
Vertical Design load	5	22k	22,340	.2344	P
Vertical Design load	6	22k	22,260	.2188	P
Vertical Design load	7	22k	22,320	.2344	P
Vertical Design load	8	22k	22,194	.2031	P
Vertical Design load	9	22k	22,466	.2187	P
Vertical Design load	10	22k	22,590	.2344	P
Vertical Test load	1	33,750	33,790	.4063	P

Vertical Box Test	Cycle #	Design Load Requirement (lbs)	Design Load Results (lbs)	Deflection (0.500 max)	Results (P/F)
Vertical Design load	1	22k	22,911	.2813	P
Vertical Design load	2	22k	22,690	.2263	P
Vertical Design load	3	22k	22,960	.2803	P
Vertical Design load	4	22k	22,960	.2663	P
Vertical Design load	5	22k	22,760	.2497	P
Vertical Design load	6	22k	22,410	.2631	P
Vertical Design load	7	22k	22,460	.2451	P
Vertical Design load	8	22k	22,321	.2660	P
Vertical Design load	9	22k	22,190	.2344	P
Vertical Design load	10	22k	22,166	.2031	P
Vertical Test load	1	33,750	34,926	.3762	P

Lateral Load Test	Cycle #	Design Load Requirement	Design Load Results (lbs)	Deflection (0.572 max)	Results (P/F)
Lateral Design load	1	2400	2409	.0018	P
Lateral Design load	2	2400	2520	.0090	P
Lateral Design load	3	2400	2480	.037	P
Lateral Design load	4	2400	2442	.029	P
Lateral Design load	5	2400	2460	.034	P
Lateral Design load	6	2400	2450	.039	P
Lateral Design load	7	2400	2521	.036	P
Lateral Design load	8	2400	2490	.038	P
Lateral Design load	9	2400	2488	.040	P
Lateral Design load	10	2400	2467	.023	P
Lateral Test load	1	3600	3840	.2329	P

Results of Analysis

Product adhered to Test specifications

☒ Yes

☐ No

Corrective/Preventive Action Created

☐ Yes **CAR#** _____

☒ No

Comments:

Pass

Concerns:

None

Suggestions

None

Quality Control:

Homero furs

Date:

11/15/22



2522 Kansas Avenue • Riverside, CA 92507 USA

December 12, 2022

This is to certify that the Purpose of Test, Description of Test Unit, Load Test on ANSI/SCTE 77-2013- Tier 22 Series and corresponding results as related in American Enclosures report of test titled:

LOAD TESTING CERTIFICATION

ANSI/SCTE 77-2013- Tier 22 SERIES

Loading Tests

APC132418

Test Date: November 15, 2022

Depict a true and factual account of events to the best of my knowledge and belief.

Authorized Testing, Inc.

By


Derek R. Gaytan, Quality Manager

A Notary Public or other officer completing this certificate verifies only the identity of the individual who signed the document to which this certificate is attached, and not the truthfulness, accuracy, or validity of that document.

STATE OF CALIFORNIA


} ss.


COUNTY OF RIVERSIDE

On this the **12th day of December 2022**, before me **ALISSA M. GRIMES**, the undersigned Notary Public, personally appeared **Derek R. Gaytan**, who proved to me on the basis of satisfactory evidence to be the person whose name is subscribed to the within instrument and acknowledged to me that he executed the same in his authorized capacity, and that by his signature on the instrument the person, or entity upon behalf of which the person acted, executed the instrument.

I certify under PENALTY OF PERJURY under the laws of the State of California that the foregoing paragraph is true and correct.

WITNESS my hand and official seal.




Notary Public

Date: 11/15/22 Time _____ **Product Compliance Analysis**

Laboratory Personnel: _____ Position: _____

Item Description: 10PC 132418 Polymer Concrete

Test Specification: ANSI/SCTE 77-2013 ☐ Tier 15 ☒ Tier 22 Referenced Work Instruction: ANSI/SCTE 77-2013

Calibrated Instruments: Tara T1504079 Load Cell – Miltutoyo Digital Indicator SN 17206067 Or SN 19228292

Vertical Cover Load	Cycle #	Design Load Requirement (lbs)	Design Load Results (lbs)	Deflection (0.500 max)	Results (P/F)
Vertical Design load	1	22k	22,229	.0	P
Vertical Design load	2	22k	22,586	.0	P
Vertical Design load	3	22k	22,438	.0	P
Vertical Design load	4	22k	22,760	.0	P
Vertical Design load	5	22k	22,840	.0	P
Vertical Design load	6	22k	22,696	.0	P
Vertical Design load	7	22k	22,366	.0	P
Vertical Design load	8	22k	22,588	.0	P
Vertical Design load	9	22k	22,416	.0	P
Vertical Design load	10	22k	22,101	.0	P
Vertical Test load	1	33,750	33,890	.0	P

Vertical Box Test	Cycle #	Design Load Requirement (lbs)	Design Load Results (lbs)	Deflection (0.500 max)	Results (P/F)
Vertical Design load	1	22k			P
Vertical Design load	2	22k			P
Vertical Design load	3	22k			P
Vertical Design load	4	22k			P
Vertical Design load	5	22k			P
Vertical Design load	6	22k			P
Vertical Design load	7	22k			P
Vertical Design load	8	22k			P
Vertical Design load	9	22k			P
Vertical Design load	10	22k			P
Vertical Test load	1	33,750			P

Too Small For test

Lateral Load Test	Cycle #	Design Load Requirement	Design Load Results (lbs)	Deflection (0.572 max)	Results (P/F)
Lateral Design load	1	2400			P
Lateral Design load	2	2400			P
Lateral Design load	3	2400			P
Lateral Design load	4	2400			P
Lateral Design load	5	2400			P
Lateral Design load	6	2400			P
Lateral Design load	7	2400			P
Lateral Design load	8	2400			P
Lateral Design load	9	2400			P
Lateral Design load	10	2400			P
Lateral Test load	1	3600			P

Too Small For test

Results of Analysis

Product adhered to Test specifications

☒ Yes

☐ No

Corrective/Preventive Action Created

☐ Yes **CAR#** _____

☒ No

Comments:

Pass

Concerns:

Can't run vertical/ Box test box too small/
For test

Suggestions

Can't run lateral test, box too small For test

Quality Control: _____

Date: _____



2522 Kansas Avenue • Riverside, CA 92507 USA

December 12, 2022

This is to certify that the Purpose of Test, Description of Test Unit, Load Test on ANSI/SCTE 77-2013- Tier 22 Series and corresponding results as related in American Enclosures report of test titled:

LOAD TESTING CERTIFICATION

ANSI/SCTE 77-2013- Tier 22 SERIES

Loading Tests

APC484848

Test Date: November 15, 2022

Depict a true and factual account of events to the best of my knowledge and belief.

Authorized Testing, Inc.

By

Derek R. Gaytan, Quality Manager

A Notary Public or other officer completing this certificate verifies only the identity of the individual who signed the document to which this certificate is attached, and not the truthfulness, accuracy, or validity of that document.

STATE OF CALIFORNIA


} ss.

COUNTY OF RIVERSIDE

On this the **12th day of December 2022**, before me **ALISSA M. GRIMES**, the undersigned Notary Public, personally appeared **Derek R. Gaytan**, who proved to me on the basis of satisfactory evidence to be the person whose name is subscribed to the within instrument and acknowledged to me that he executed the same in his authorized capacity, and that by his signature on the instrument the person, or entity upon behalf of which the person acted, executed the instrument.

I certify under PENALTY OF PERJURY under the laws of the State of California that the foregoing paragraph is true and correct.

WITNESS my hand and official seal.



Notary Public

Date: 11/15/22 Time _____ **Product Compliance Analysis**

Laboratory Personnel: Harmer B Position: _____

Item Description: OPC 484848 Polymer Concrete

Test Specification: ANSI/SCTE 77-2013 ☐ Tier 15 ☒ Tier 22 Referenced Work Instruction: ANSI/SCTE 77-2013

Calibrated Instruments: Tara T1504079 Load Cell – Miltutoyo Digital Indicator SN 17206067 Or SN 19228292

Vertical Cover Load	Cycle #	Design Load Requirement (lbs)	Design Load Results (lbs)	Deflection (0.500 max)	Results (P/F)
Vertical Design load	1	22k	22,540	.2501	P
Vertical Design load	2	22k	22,690	.3060	P
Vertical Design load	3	22k	22,718	.2969	P
Vertical Design load	4	22k	22,980	.3101	P
Vertical Design load	5	22k	23,190	.3104	P
Vertical Design load	6	22k	22,639	.2902	P
Vertical Design load	7	22k	22,410	.2689	P
Vertical Design load	8	22k	22,177	.2662	P
Vertical Design load	9	22k	22,660	.2720	P
Vertical Design load	10	22k	22,890	.2747	P
Vertical Test load	1	33,750	34,960	.4209	P

Vertical Box Test	Cycle #	Design Load Requirement (lbs)	Design Load Results (lbs)	Deflection (0.500 max)	Results (P/F)
Vertical Design load	1	22k	22,880	.2016	P
Vertical Design load	2	22k	22,520	.2210	P
Vertical Design load	3	22k	22,680	.2120	P
Vertical Design load	4	22k	22,724	.2525	P
Vertical Design load	5	22k	22,888	.2527	P
Vertical Design load	6	22k	22,660	.2039	P
Vertical Design load	7	22k	22,360	.2013	P
Vertical Design load	8	22k	22,441	.2018	P
Vertical Design load	9	22k	22,466	.2022	P
Vertical Design load	10	22k	22,520	.2068	P
Vertical Test load	1	33,750	33,980	.3760	P

Lateral Load Test	Cycle #	Design Load Requirement	Design Load Results (lbs)	Deflection (0.572 max)	Results (P/F)
Lateral Design load	1	2400	2410	.1095	P
Lateral Design load	2	2400	2410	.1163	P
Lateral Design load	3	2400	2590	.1124	P
Lateral Design load	4	2400	2492	.1297	P
Lateral Design load	5	2400	2453	.1162	P
Lateral Design load	6	2400	2439	.1066	P
Lateral Design load	7	2400	2466	.1238	P
Lateral Design load	8	2400	2488	.1266	P
Lateral Design load	9	2400	2520	.1290	P
Lateral Design load	10	2400	2560	.1310	P
Lateral Test load	1	3600	3719	.1957	P

JH American Enclosures LLC
8530 E Hwy 67 Bldg C
Alvarado, TX 76009
Jh_american@yahoo.com

JH American Enclosures
Made from over 30 years of experience

Product Compliance Analysis

Results of Analysis

Product adhered to Test specifications

☒ Yes

☐ No

Corrective/Preventive Action Created

☐ Yes

CAR#

☒ No

Comments:

Pass

Concerns:

None

Suggestions

None

Quality Control:

Hanna B

Date:

11/15/22



2522 Kansas Avenue • Riverside, CA 92507 USA

December 12, 2022

This is to certify that the Purpose of Test, Description of Test Unit, Load Test on ANSI/SCTE 77-2013- Tier 22 Series and corresponding results as related in American Enclosures report of test titled:

LOAD TESTING CERTIFICATION

ANSI/SCTE 77-2013- Tier 22 SERIES

Loading Tests

APC173024

Test Date: November 15, 2022

Depict a true and factual account of events to the best of my knowledge and belief.

Authorized Testing, Inc.

By


Derek R. Gaytan, Quality Manager

A Notary Public or other officer completing this certificate verifies only the identity of the individual who signed the document to which this certificate is attached, and not the truthfulness, accuracy, or validity of that document.

STATE OF CALIFORNIA


} ss.


COUNTY OF RIVERSIDE

On this the **12th day of December 2022**, before me **ALISSA M. GRIMES**, the undersigned Notary Public, personally appeared **Derek R. Gaytan**, who proved to me on the basis of satisfactory evidence to be the person whose name is subscribed to the within instrument and acknowledged to me that he executed the same in his authorized capacity, and that by his signature on the instrument the person, or entity upon behalf of which the person acted, executed the instrument.

I certify under PENALTY OF PERJURY under the laws of the State of California that the foregoing paragraph is true and correct.

WITNESS my hand and official seal.




Notary Public

Date: 11/15/22 Time _____ **Product Compliance Analysis**

Laboratory Personnel: _____ Position: _____

Item Description: NAC 172024 Polymer Concrete

Test Specification: ANSI/SCTE 77-2013 ☐ Tier 15 ☒ Tier 22 Referenced Work Instruction: ANSI/SCTE 77-2013

Calibrated Instruments: Tara T1504079 Load Cell – Miltutoyo Digital Indicator SN 17206067 Or SN 19228292

Vertical Cover Load	Cycle #	Design Load Requirement (lbs)	Design Load Results (lbs)	Deflection (0.500 max)	Results (P/F)
Vertical Design load	1	22k	22,268	.1795	P
Vertical Design load	2	22k	22,480	.1808	P
Vertical Design load	3	22k	22,460	.1837	P
Vertical Design load	4	22k	22,110	.1843	P
Vertical Design load	5	22k	22,710	.1868	P
Vertical Design load	6	22k	22,490	.1816	P
Vertical Design load	7	22k	22,341	.1788	P
Vertical Design load	8	22k	22,688	.185	P
Vertical Design load	9	22k	22,178	.1775	P
Vertical Design load	10	22k	22,198	.1776	P
Vertical Test load	1	33,750	34,780	.2012	P

Vertical Box Test	Cycle #	Design Load Requirement (lbs)	Design Load Results (lbs)	Deflection (0.500 max)	Results (P/F)
Vertical Design load	1	22k	22,360	.2143	P
Vertical Design load	2	22k	22,560	.2107	P
Vertical Design load	3	22k	22,595	.2195	P
Vertical Design load	4	22k	22,360	.2164	P
Vertical Design load	5	22k	22,195	.2107	P
Vertical Design load	6	22k	22,349	.2124	P
Vertical Design load	7	22k	22,178	.2107	P
Vertical Design load	8	22k	22,560	.2144	P
Vertical Design load	9	22k	22,560	.2173	P
Vertical Design load	10	22k	22,560	.2144	P
Vertical Test load	1	33,750	34,090	.2276	P

Lateral Load Test	Cycle #	Design Load Requirement	Design Load Results (lbs)	Deflection (0.572 max)	Results (P/F)
Lateral Design load	1	2400	2426	.3560	P
Lateral Design load	2	2400	2472	.3970	P
Lateral Design load	3	2400	2512	.4325	P
Lateral Design load	4	2400	2609	.4610	P
Lateral Design load	5	2400	2570	.4249	P
Lateral Design load	6	2400	2560	.4416	P
Lateral Design load	7	2400	2460	.3986	P
Lateral Design load	8	2400	2538	.4560	P
Lateral Design load	9	2400	2624	.4490	P
Lateral Design load	10	2400	2506	.4420	P
Lateral Test load	1	3600	3620	.4963	P

Results of Analysis

Product adhered to Test specifications

☒ Yes

☐ No

Corrective/Preventive Action Created

☐ Yes **CAR#** _____

☒ No

Comments:

Pass

Concerns:

None

Suggestions

None

Quality Control:

[Signature]

Date:

11/15/22



2522 Kansas Avenue • Riverside, CA 92507 USA

December 12, 2022

This is to certify that the Purpose of Test, Description of Test Unit, Load Test on ANSI/SCTE 77-2013- Tier 22 Series and corresponding results as related in American Enclosures report of test titled:

LOAD TESTING CERTIFICATION

ANSI/SCTE 77-2013- Tier 22 SERIES

Loading Tests

APC3011824

Test Date: November 15, 2022

Depict a true and factual account of events to the best of my knowledge and belief.

Authorized Testing, Inc.

By

Derek R. Gaytan, Quality Manager

A Notary Public or other officer completing this certificate verifies only the identity of the individual who signed the document to which this certificate is attached, and not the truthfulness, accuracy, or validity of that document.

STATE OF CALIFORNIA


} ss.

COUNTY OF RIVERSIDE

On this the **12th day** of **December 2022**, before me **ALISSA M. GRIMES**, the undersigned Notary Public, personally appeared **Derek R. Gaytan**, who proved to me on the basis of satisfactory evidence to be the person whose name is subscribed to the within instrument and acknowledged to me that he executed the same in his authorized capacity, and that by his signature on the instrument the person, or entity upon behalf of which the person acted, executed the instrument.

I certify under PENALTY OF PERJURY under the laws of the State of California that the foregoing paragraph is true and correct.

WITNESS my hand and official seal



Notary Public

Date: 11/15/22 Time: _____

Product Compliance Analysis

Laboratory Personnel: Homer B Position: GAC

Item Description: OPC 304824 Polymer Concrete

Test Specification: ANSI/SCTE 77-2013 ☐ Tier 15 ☒ Tier 22 Referenced Work Instruction: ANSI/SCTE 77-2013

Calibrated Instruments: Tara T1504079 Load Cell – Miltutoyo Digital Indicator SN 17206067 Or SN 19228292

Vertical Cover Load	Cycle #	Design Load Requirement (lbs)	Design Load Results (lbs)	Deflection (0.500 max)	Results (P/F)
Vertical Design load	1	22k	22,750	.2115	P
Vertical Design load	2	22k	22,430	.2168	P
Vertical Design load	3	22k	22,550	.2126	P
Vertical Design load	4	22k	22,450	.2127	P
Vertical Design load	5	22k	22,750	.2114	P
Vertical Design load	6	22k	22,680	.1970	P
Vertical Design load	7	22k	22,640	.2079	P
Vertical Design load	8	22k	22,670	.1967	P
Vertical Design load	9	22k	22,430	.1941	P
Vertical Design load	10	22k	22,280	.1936	P
Vertical Test load	1	33,750	33,840	.4688	P

Vertical Box Test	Cycle #	Design Load Requirement (lbs)	Design Load Results (lbs)	Deflection (0.500 max)	Results (P/F)
Vertical Design load	1	22k	22,240	.39	P
Vertical Design load	2	22k	22,440	.00	P
Vertical Design load	3	22k	22,680	.00	P
Vertical Design load	4	22k	22,442	.00	P
Vertical Design load	5	22k	22,490	.005	P
Vertical Design load	6	22k	22,970	.0015	P
Vertical Design load	7	22k	22,954	.0015	P
Vertical Design load	8	22k	22,879	.0015	P
Vertical Design load	9	22k	22,609	.0029	P
Vertical Design load	10	22k	22,660	.0029	P
Vertical Test load	1	33,750	37,880	.0050	P

Lateral Load Test	Cycle #	Design Load Requirement	Design Load Results (lbs)	Deflection (0.572 max)	Results (P/F)
Lateral Design load	1	2400	2480	.3438	P
Lateral Design load	2	2400	2500	.3890	P
Lateral Design load	3	2400	2470	.4063	P
Lateral Design load	4	2400	2490	.4212	P
Lateral Design load	5	2400	2440	.4218	P
Lateral Design load	6	2400	2530	.4375	P
Lateral Design load	7	2400	2460	.4210	P
Lateral Design load	8	2400	2650	.4215	P
Lateral Design load	9	2400	2290	.3892	P
Lateral Design load	10	2400	2310	.4215	P
Lateral Test load	1	3600	3790	.5633	P

JH American Enclosures LLC
8330 E Hwy 67 Bldg C
Alvarado, TX 76009
Jh_american@yahoo.com

JH American Enclosures
Made from over 30 years of experience

Product Compliance Analysis

Results of Analysis

Product adhered to Test specifications

☒ Yes

☐ No

Corrective/Preventive Action Created

☐ Yes **CAR#** _____

☒ No

Comments:

Pass

Concerns:

None

Suggestions

None

Quality Control:

Homer Perry B

Date:

11/15/22



2522 Kansas Avenue • Riverside, CA 92507 USA

December 12, 2022

This is to certify that the Purpose of Test, Description of Test Unit, Load Test on ANSI/SCTE 77-2013- Tier 22 Series and corresponding results as related in American Enclosures report of test titled:

LOAD TESTING CERTIFICATION
ANSI/SCTE 77-2013- Tier 22 SERIES
Loading Tests
APC366036

Test Date: November 15, 2022

Depict a true and factual account of events to the best of my knowledge and belief.

Authorized Testing, Inc.

By


Derek R. Gaytan, Quality Manager

A Notary Public or other officer completing this certificate verifies only the identity of the individual who signed the document to which this certificate is attached, and not the truthfulness, accuracy, or validity of that document.

STATE OF CALIFORNIA


} ss.


COUNTY OF RIVERSIDE

On this the **12th day of December 2022**, before me **ALISSA M. GRIMES**, the undersigned Notary Public, personally appeared **Derek R. Gaytan**, who proved to me on the basis of satisfactory evidence to be the person whose name is subscribed to the within instrument and acknowledged to me that he executed the same in his authorized capacity, and that by his signature on the instrument the person, or entity upon behalf of which the person acted, executed the instrument.

I certify under PENALTY OF PERJURY under the laws of the State of California that the foregoing paragraph is true and correct.

WITNESS my hand and official seal.




Notary Public

Date: 11/15/22 Time _____

Product Compliance Analysis

Laboratory Personnel: Homer J Position: _____

Item Description: NP 366036 Polymer Concrete

Test Specification: ANSI/SCTE 77-2013 ☐ Tier 15 ☒ Tier 22 Referenced Work Instruction: ANSI/SCTE 77-2013

Calibrated Instruments: Tara T1504079 Load Cell – Miltutoyo Digital Indicator SN 17206067 Or SN 19228292

Vertical Cover Load	Cycle #	Design Load Requirement (lbs)	Design Load Results (lbs)	Deflection (0.500 max)	Results (P/F)
Vertical Design load	1	22k	22,460	,2696	P
Vertical Design load	2	22k	22,780	,2724	P
Vertical Design load	3	22k	22,680	,2722	P
Vertical Design load	4	22k	22,928	,2752	P
Vertical Design load	5	22k	24,690	,2963	P
Vertical Design load	6	22k	23,961	,2876	P
Vertical Design load	7	22k	22,488	,2699	P
Vertical Design load	8	22k	22,481	,2698	P
Vertical Design load	9	22k	22,560	,2708	P
Vertical Design load	10	22k	22,490	,2698	P
Vertical Test load	1	33,750	33,960	,4076	P

Vertical Box Test	Cycle #	Design Load Requirement (lbs)	Design Load Results (lbs)	Deflection (0.500 max)	Results (P/F)
Vertical Design load	1	22k	22,472	,2696	P
Vertical Design load	2	22k	22,660	,2720	P
Vertical Design load	3	22k	22,881	,2746	P
Vertical Design load	4	22k	22,431	,2692	P
Vertical Design load	5	22k	22,680	,2722	P
Vertical Design load	6	22k	22,668	,2721	P
Vertical Design load	7	22k	22,441	,2693	P
Vertical Design load	8	22k	22,520	,2703	P
Vertical Design load	9	22k	22,680	,2722	P
Vertical Design load	10	22k	22,844	,2754	P
Vertical Test load	1	33,750	34,520	,4147	P

Lateral Load Test	Cycle #	Design Load Requirement	Design Load Results (lbs)	Deflection (0.572 max)	Results (P/F)
Lateral Design load	1	2400	2560	,2304	P
Lateral Design load	2	2400	2596	,2364	P
Lateral Design load	3	2400	2441	,2196	P
Lateral Design load	4	2400	2438	,2196	P
Lateral Design load	5	2400	2567	,2310	P
Lateral Design load	6	2400	2938	,2645	P
Lateral Design load	7	2400	2467	,2221	P
Lateral Design load	8	2400	2566	,2310	P
Lateral Design load	9	2400	2594	,2296	P
Lateral Design load	10	2400	2589	,2330	P
Lateral Test load	1	3600	3790	,2431	P

JH American Enclosures LLC
8330 E Hwy 67 Bldg C
Alvarado, TX 76009
Jh_american@yahoo.com

JH American Enclosures
Made from over 30 years of experience

Product Compliance Analysis

Results of Analysis

Product adhered to Test specifications

☒ Yes

☐ No

Corrective/Preventive Action Created

☐ Yes **CAR#** _____

☒ No

Comments:

Pass

Concerns:

None

Suggestions

None

Quality Control:

[Signature]

Date:

11/15/22